

Evaluation of Impression Difference of a Domestic Mobile Manipulator with Autonomous and/or Remote Control in Fetch-and-Carry Tasks

Takashi Yamamoto^{a,c*}, Hiroaki Yaguchi^b, Shohei Kato^c, and Hiroyuki Okada^d

^a*Frontier Research Center, Toyota Motor Corporation, Toyota, Aichi, Japan;*

^b*Kushinada Tech. Co., Ltd., Toshima, Tokyo, Japan;*

^c*Graduate School of Engineering, Nagoya Institute of Technology, Nagoya, Aichi, Japan;*

^d*Faculty of Engineering, Tamagawa University, Machida, Tokyo, Japan*

*Corresponding author. E-mail: tyamamoto@mail.toyota.co.jp

Various studies on autonomous robots that perform physical tasks in living environments are being conducted at present to solve the social problems of an aging society with a low birth rate. However, because it remains difficult for all robots to work autonomously in complicated environments, remote control robots may be useful for practical applications. As the purpose of remote control robots is to make direct connections between the operator and user, they may reduce affinity between the robot and the user. In this study, we define autonomous remote control robots with the aspects of both autonomy and remote operation explicitly. Affinity is compared among autonomous remote control robots, remote control robots, and autonomous robots, through controlled experiments on interactions in fetch-and-carry tasks using a domestic mobile manipulator, Human Support Robot, on a test field that is compliant with the World Robot Summit 2020 Rulebook. The results demonstrate that affinity exhibits the following order: autonomous robots, autonomous remote control robots, and remote control robots. Considering that autonomous robots remain under development, autonomous remote control robots may be beneficial for expanding the abilities of physical tasks and social acceptance.

Keywords: human-robot interaction; remote control robot; autonomous robot; mobile manipulation; personal and service robotics

1. Introduction

The development of robots that autonomously perform physical tasks in environments with people (autonomous robots) has been actively researched [1, 2, 3, 4]. Autonomous robots may provide a solution for various social problems, such as labor force shortages owing to the aging population with a low birth rate, release from monotonous or harsh work for people, support independent living for elderly or disabled people, and housework support for busy people. However, because it remains difficult for robots to perform all tasks autonomously in complex environments, robots that are remotely controlled by operators (remote control robots) are considered to be useful for practical applications. Moreover, as the data from remote operations are available for the learning of robots, remote control robots may provide an effective means to promote autonomous robot technology [5]. However, for such robots to be widely used in people's lives, it is important to improve the social acceptance of robots [6, 7, 8, 9]. The relationship between robots and humans has been regarded as one of the key points for social acceptance. Within the above context, we study the effects of autonomous and remote control functions on the relationship between user and robot. In this paper, we refer to the affinity for the robot, which means that the robot makes the user feel friendliness, a positive impression, and a good relationship. We assume that a higher affinity with users will result in the improvement of social acceptance to a greater extent. As noted previously, at present, remote control robots are considered to be more practical and useful than autonomous robots in many physical tasks that cannot be completed by robots autonomously. However, as the relationship between remote operator and user is centered on the remote control robot, the presence of the robot may be obscured for the




Figure 1. Configuration of autonomous remote control robot

user. As a result, the affinity between the user and the robot may be reduced. In this study, we present a new robot configuration (the autonomous remote control robot; Figure 1) in addition to the remote control and autonomous robots. We perform a comparative study of the affinity for robots among these three configurations with physical entities.

The autonomous remote control robot is defined as a robot that has both the presence of the remote operator (operator agent) and the autonomous robot (robot agent) inside of it, as shown in Figure 1. Both the operator agent and robot agent exist explicitly and share knowledge and instructions regarding physical tasks through interactions among three parties, namely the above two agents and the user who receives the services. To explain Figure 1, for example, we assume a case where user U asks robot R to bring them something to drink. When U asks R to do the task, the robot agent confirms and replies as a dialogue with U . If the task is difficult to perform autonomously, the robot agent asks the operator agent for assistance as an explicit dialogue for U . In case the robot agent does not know where to go (e.g., kitchen), the robot agent asks the operator agent, and the operator agent tells the robot agent about the name of the place (kitchen) as an explicit dialogue for U . Or, if the robot agent cannot grasp the target object, the robot agent asks the operator agent for support as an explicit dialogue for U and the operator agent takes control of the physical body of R and operates it explicitly for U . The robot agent and the operator agent share one common physical body and control it based on arbitration through explicit dialogue for U , while they and the user communicate mutually to bring something to drink as a physical service to U .

Numerous examples of remote control robots with autonomous functions to support the operations of remote operators are available. However, as mentioned previously, the concept and purpose of the autonomous remote control robot differ from these. It can be stated that new value is offered by the configuration of the autonomous remote control robot if higher affinity can be obtained than previous remote control robots. Furthermore, if autonomous robots can achieve the same or higher affinity than autonomous remote control robots, it is reasonable to anticipate that autonomous remote control robots will first be implemented in society, and their autonomous functions will be improved sequentially to maintain and develop both abilities for physical tasks and the affinity for users simultaneously. To demonstrate this, we implemented remote control functions, autonomous functions, and autonomous remote control functions in a domestic mobile manipulator. Under the same environment, with the same hardware and tasks with the same purpose, we confirmed the difference between their affinities and which configuration exhibited the highest affinity through subject experiments. Robots that combine

autonomous functions and remote control functions to perform physical tasks have been developed continuously. For example, a system was developed that performs fetch-and-carry tasks (FCTs) by tapping or handwriting a line on a target object on the screen of a tablet PC [10]. Furthermore, in subsequent studies [11], a robot learning method was realized by teaching simple furniture operations through the tablet. Although autonomous functions were mentioned in these studies, their purpose was mainly to provide easier methods for remote operators to control robots, and the affinity between user and robot was not particularly considered. The research in [12] focused on onomatopoeia emitted by a robot to assist the operation of a remote operator, while that in [13] proposed comprehensive sensory sharing through a remote robot. In both cases, the relationship between the remote operator and the robot was the main focus. Various studies have been conducted on communication between robots and humans. For example, research on single robot versus single user [14], single robot versus multiple users [15, 16], and multiple robots versus single user [17] has been presented. However, these works mainly focused on autonomous communication robots and not robots that perform physical tasks. Moreover, the explicit coexistence of the operator and autonomy of the robot was not studied. In [18], it was experimentally verified that a user feels the presence of a remote operator in dialogues between the remote operator and user via the robot, even if autonomous dialogues are inserted in the middle. However, the user impression of physical robots with the agent and remote operator was not evaluated. In [19], it was explained that, when a subject interacts with a remote-controlled robot through dialogue or body contact, the subject tends to sense interaction with the robot itself, and not the remote operator, even if the information is received in advance. However, the main function of this robot was verbal and physical contact communication and not physical task executions. Furthermore, the explicit coexistence of the robot and operator agents was not studied. The study of [20] demonstrated that an agent could move to various devices, including robots, so that the user can interact smoothly with the devices. However, the user impression of physical robots with the agent and remote operator was not evaluated.

In this paper, we aim to clarify the impression difference among remote control, autonomous, and autonomous remote control robots with FCTs in the home environment. We assume that the affinity of autonomous remote control robots is higher than that of remote control robots and less than or equal to that of autonomous robots. If the above assumption holds, autonomous remote control robots could be practical and beneficial in terms of compatibility between social acceptance and task performance, as mentioned earlier in this section.

The remainder of this paper is organized as follows. Section 2 describes the robot, target task, and implemented system. In this study, we consider an FCT, which is the basis of all physical tasks. We attempt to define the conditions of the task as clearly as possible for future research. In Section 3, we explain the design of the subject experiments to compare autonomous remote control functions with remote control functions and autonomous functions. We evaluate the results using two methods, such as the semantic differential (SD) method and ranking method. In Section 4, we present the experimental results. With the data from the subjects, we objectively determine the factors related to the affinity. In Section 5, we discuss the results, and in Section 6, we provide the conclusions of the study.

2. System Design and Target Task

2.1 *Robot and Control Mode*

We used the Human Support Robot (HSR) [3] in Figure 2 for this study. The HSR is the research platform of a domestic mobile manipulator with functionality, safety, and a small physique for performing physical tasks in living environments. It has been used in various research projects and international robot competitions [21, 22, 23, 24, 25, 26, 27].

In this study, we implemented the following three control modes, selectively on the same HSR.




Figure 2. HSR

M1 : Remote control mode:

R performs physical tasks by the remote control of C .

M2 : Autonomous control mode:

R performs physical tasks autonomously by commands from C or U .

M3 : Autonomous remote control mode:

R performs physical tasks by both the remote control of C and autonomous control, as per the autonomous remote control robot illustrated in Figure 1.

We denote R as the robot, E as the environment in which R performs tasks, U as the user who receives services from R , C as the operator who controls R remotely, O as the target object, which R fetches and carries to U , P as the place in which O exists, and $\Omega_e = \{U, C, R\}$ as the set of the three parties. In real cases, C and U may even be the same person, whereby U receives the service of R by own remote control.

The modes M1, M2, and M3 corresponds to remote control, autonomous and autonomous remote control robots, respectively.

2.2 Target Task

Although the FCT is a simple and basic task, diverse cases exist depending on the conditions. Firstly, we classify the extensive conditions of the FCT and clarify the scope of this research.

2.2.1 Definition of Task

We focus on an FCT in which R fetches and carries O to U because it includes major technical elements such as movement, recognition, and grasping; moreover, it can form the basis of any complex physical task. Next, we divide the FCT into sub-tasks (STs), as follows:

ST1 : Go to P

ST2 : Take O

ST3 : Go to U

ST4 : Hand O to U

As illustrated in Figure 3, each ST is sequentially executed in the FCT. Specifically, R moves to P (ST1), takes O (ST2), moves to U (ST3), and hands O to U (ST4).

We first clarify the combination of knowledge and abilities of U , C , and R generically. For example, it is difficult for R to move autonomously in ST1 and ST3 if R does not know the information of E . In fact, numerous combinations of the knowledge and abilities of U , C , and R exist. We define Ω_p as the set of all combinations of knowledge and abilities thereof. One element $i \in \Omega_p$ is denoted by ‘pattern i ’. Furthermore, we define $\Omega_k = \{K_O, K_P, K_M, K_G\}$ as the set of four types of knowledge and abilities and a two-valued logic function (referred to as




Figure 3. STs of FCT

the ‘condition function’) on pattern i , $L_i(x, y)$ ($x \in \Omega_e = \{U, C, R\}$, $y \in \Omega_k$), as follows:

- $y = K_O$: Initial knowledge of object

In the case where x knows O initially or decides O by itself, the condition function $L_i(x, K_O) = 1$ (TRUE). If not, $L_i(x, K_O) = 0$ (FALSE).

In other words, K_O represents the initiative to decide the target object O of the task. Even if $L_i(x, K_O) = 0$, it is possible for x to know O , after hearing what O is from the others assuming x can understand what O is. We assume that $L_i(R, K_O) = 1$ means that R knows what to grasp from the beginning of the task without hearing from U or C and it does not mean that R has the ability to detect O in E . The ability is included in the condition of K_G mentioned below.

- $y = K_P$: Initial knowledge of place

In the case where x knows where P is initially, the condition function $L_i(x, K_P) = 1$ (TRUE). If not, $L_i(x, K_P) = 0$ (FALSE). Even if $L_i(x, K_P) = 0$, it is possible for x to share the information of P , after hearing P in the case where x has the map of E with P .

- $y = K_M$: Ability of movement

In the case where x can cause R to move to any acceptable goal in E by its order or control, the condition function $L_i(x, K_M) = 1$ (TRUE). If not, $L_i(x, K_M) = 0$ (FALSE). It is possible for R to move autonomously if $L_i(R, K_M) = 1$.

- $y = K_G$: Ability of grasping

In the case where x can cause R to grasp any acceptable object by its order or control, the condition function $L_i(x, K_G) = 1$ (TRUE). If not, $L_i(x, K_G) = 0$ (FALSE). We assume that it is possible for R to grasp any acceptable object autonomously along with the ability to detect it in E in case that $L_i(R, K_G) = 1$.

In a general FCT, there are 4096 patterns ($= (2^4)^3$) based on simple combinations of the four conditions of $\Omega_k = \{K_O, K_P, K_M, K_G\}$. However, the number of patterns that should be evaluated can be decreased by setting the following reasonable assumptions:

- Only one of U, C, R has the knowledge and abilities of $\Omega_k = \{K_O, K_P, K_M, K_G\}$.

In this case, the following condition is satisfied:

$$\forall y \in \Omega_k, L_i(U, y) \oplus L_i(C, y) \oplus L_i(R, y) = 1. \quad (1)$$

Table 1. Value of condition function and control mode for each pattern

	U				C				R				Mode
	K_O	K_P	K_M	K_G	K_O	K_P	K_M	K_G	K_O	K_P	K_M	K_G	
PN1	1	0	0	0	0	1	1	1	0	0	0	0	M1
PN2	1	0	0	0	0	1	1	0	0	0	0	1	M3
PN3	1	0	0	0	0	0	0	1	0	1	1	0	M3
PN4	1	0	0	0	0	0	0	0	0	1	1	1	M2

Owing to this condition, the redundancy of the roles of U , C , and R is eliminated.

b) C or R has the ability of movement if it has knowledge of the place.

In this case, the following condition is satisfied:

$$\forall x \in \{C, R\}, L_i(x, K_P) \rightarrow L_i(x, K_M) = 1. \quad (2)$$

We can assume that C or R has the map of E if it has knowledge of the place. This means that C can control R or R can move autonomously using the map of E .

2.2.2 Classification of Pattern for Control Mode

We can classify each pattern i as a control mode, depending on the ability of R , as follows:

- Classification condition of remote control mode (M1):

If the following condition is satisfied, the pattern i is classified as M1 because R cannot move and grasp objects autonomously.

$$\neg(L_i(R, K_M) \vee L_i(R, K_G)) = 1. \quad (3)$$

- Classification condition of autonomous mode (M2):

If the following condition is satisfied, the pattern i is classified as M2 because R can move and grasp objects autonomously.

$$L_i(R, K_M) \wedge L_i(R, K_G) = 1. \quad (4)$$

- Classification condition of autonomous remote control mode (M3):

If the following condition is satisfied, the pattern i is classified as M3 because R can only perform either autonomous movement or autonomous grasping.

$$L_i(R, K_M) \oplus L_i(R, K_G) = 1. \quad (5)$$

2.2.3 Selection of User and Evaluation Task

There are various cases for the conditions of user U . In the evaluation of this research, we select the following conditions:

$$L_i(U, K_O) = 1, \quad (6)$$

$$\forall y \in \{K_P, K_M, K_G\}, L_i(U, y) = 0. \quad (7)$$

The above conditions mean that U only orders O , whereas C controls R remotely or R acts autonomously. We denote the subset Ω_p^s of patterns satisfying the conditions of equations (1), (2), (6), and (7) as $\Omega_p^s \subset \Omega_p$. As a result, four patterns exist in Ω_p^s , which is denoted as $\Omega_p^s = \{PN_1, PN_2, PN_3, PN_4\}$. Table 1 displays the values of the condition functions and the control mode classified by (3), (4), and (5) for each pattern in Ω_p^s .

We describe specific examples that match the conditions of Ω_p^s to ensure that these patterns are realistic, as follows:

PN_1 : In this case, C has K_P , K_M , and K_G and the control mode is M1. As an example, there is a case in which helper C fully supports U with limb disorders, with remote control of R at U 's home.

PN_2 : In this case, C has K_P and K_M , and R has K_G . The control mode is M3. As an example, we assume the following situation. Elderly U starts to reside at a care home for the first time with his robot R and asks R to bring a product O , which R knows. Here, R does not know E and P . The remote helper C can only make R go to the location, following which R can find O and take it.

PN_3 : In this case, R has K_P and K_M , and C has K_G . The control mode is M3. As an example, we assume the following situation. Helper C remotely supports elderly U at U 's house for the first time. U requests O from R , and R moves to P autonomously. However, R cannot detect and grasp O because numerous similar objects and obstacles exist in P . Because R cannot perform autonomously, C remotely controls R to support it.

PN_4 : In this case, R has K_P , K_M , and K_G and R is a typical autonomous servant robot that can fetch and carry any accepted O requested by any U , including a healthy person, autonomously. The control mode is M2.

2.3 System Design

2.3.1 Selection of Remote Control Method

There are various means of achieving the remote control of robots, particularly for grasping objects, as explained in the following examples.

- Real-time instruction [13, 12]

In this method, C sends instructions of each movement to R in real-time. In general, remote control devices such as joysticks, wearable devices that measure the movement of C , and motion measurement sensors installed in the environment are required. If a relationship between humans replaces this method, it would be similar to the method of direct instruction by taking the opponent's hand and transmitting the action.

- Intermittent trajectory instruction [28, 29]

In this method, C sends instructions of the target trajectories to R intermittently. Once C provides initial rough information of the trajectories of R , R may modify them, adapting to the environment autonomously. For example, C indicates the target trajectory by finger operation or handwriting on the tablet screen, and R determines the actual trajectory on this basis. If this method is replaced by a relationship between humans, it would be similar to the method of gesture instruction by showing the real movement.

- Goal instruction [10, 11]

When C performs a screen tap or provides a simple drawing instruction on the tablet screen to the target, the trajectories of R are generated, and R starts to move automatically. If this method is replaced by a relationship between humans, it would be similar to the method of saying 'Take it' and pointing at the target object with a finger.

In this research, we adopt the goal instruction method, which is the easiest to operate by a remote operator and has already been developed on the HSR by the authors.

2.3.2 User Interface

In this section, we explain the user interface (UI). In this study, communication among three parties (U , C , and R) from different locations is required. Therefore, instead of speech dialogue, in which recognition failures and conversation collisions are likely to occur, we adopt a text chat UI, which is widely used in devices such as mobile phones. The text chat is used extensively for dialogue, and we believe that it poses no real problem as an alternative to oral communication. For visual instructions and confirmations, both U and C use the image of the robot camera to share visual information. Both U and C use the same UI on each PC. Figure 4 presents the UI



Figure 4. User interface




Figure 5. System configuration

image displayed on the operation PC. The left side of the screen is the camera image of R , while the right side is the text chat.

2.3.3 Overview of Implemented System

The implemented system configuration is presented in Figure 5. Comments of U and C are entered through the Chat Channel of the browser on each PC. These are interpreted by natural language processing (NLP) via the Chat Server and Bot App. In NLP, it is possible to interpret various sentence expressions by learning multiple sentences for each command in advance. The Bot App performs dialogue control based on the interpreted command information. In this case, the states and transitions of the dialogue are represented by a finite state machine. From the Bot App, comments are sent to the Chat Server, commands are sent as an ROS Topic to the robot (HSR) via the Commander, and the operation is executed. The chat system used in this study is Slack, and the NLP is Language Understanding (LUIS) from Microsoft. The robot camera image and drawing information by C are displayed on the user PC (User PC) and remote operator PC (Operator PC) from the front end of the browser via the Vision Server. The drawing information of C can be hidden on the User PC. Moreover, it is possible to send commands to the robot directly, without knowledge of the user, from the remote operator PC and to send sentences to the Chat Server as a robot. Using these mechanisms, Wizard of OZ (WOZ) tests [30] by C become possible.



Figure 6. Grasping object indication by handwritten line on screen

2.3.4 Implementation of STs

Next, we explain the implementation of each ST of the FCT described in 2.2.1. In this study, we focus on a comparative evaluation of three control modes; thus, we do not implement all control modes completely. Each ST has almost the same implementation in any control mode. Different control modes are realized by partially incorporating the WOZ test, and changing the screen or dialog contents presented to U .

- Implementation of ST1

R stores a map of the environment E , and the location P is registered. When P is specified, R autonomously moves to P using the standard two-dimensional simultaneous localization and mapping algorithm.

- Implementation of ST2

The object O is always treated as an unknown object for R . Through the camera mounted on robot R , C draws a line on O displayed on the UI screen of the Operator PC and specifies the object to be grasped by R . Figure 6 presents the Operator PC screen at the time of remote operation, where a red line drawn by C from the Operator PC is displayed on the green pen on the right. At this time, the three-dimensional position of the drawing line is measured from the information on the depth sensor mounted on R 's head. R performs the actual motion automatically after planning the grasping posture of the hand and motion of the entire body.

- Implementation of ST3

Assuming that U is always in the same location, the location of U is registered on R 's map in advance. Therefore, the implementation is the same as that of ST1.

- Implementation of ST4

U receives the object O from R 's hand after automatically moving R 's hand to the fixed position, where it is easy for U to take. R opens the hand after a force sensor mounted on the wrist of R detects the external force generated when U takes O from R 's hand.

3. Experiments

3.1 Overview of Experiments

Using the implemented system described in the previous section, interaction experiments on the three control modes by the subjects (U), robot R , and remote operator (C) were performed. Each subject answered questionnaires based on the SD method for each control mode. After the completion of the three experiments with different control modes, the subject was asked

to answer the ranking questions for each control mode based on the ranking method. In the experiment, user U was the subject, remote operator C was the developer, and robot R was the HSR. The total number of subjects was 36, consisting of 33 university engineering course students (30 males, from 18 to 22 years old, and 3 females, from 18 to 21 years old) and 3 university officers (3 females, from 41 to 50 years old). The effect of subject demographics will be discussed in subsection 4.1.1.

Firstly, the purpose of this experiment was explained to the subjects. At this time, we explained the outline of the three control modes and that each experiment in each mode would be performed sequentially on the same robot in advance. Next, we explained how to use the chat system on the User PC and allowed the subjects to get used to the operation through greetings by chatting with R and C . Prior to each experiment, the subject was told which control mode would be used. Even in actual usage scenes, it is natural for the user to know the control mode of the robot in advance. Each experiment was performed by the subject alone, while C remotely controlled R in another room. As each subject performed three experiments of the different control modes (M1, M2, and M3) sequentially, the concern arose that the order of the experiments would affect the results. Therefore, the test was performed by randomly changing the experiment order. Although the number of permutations in the three control modes was 6, each subject was randomly and equally allocated to one of six groups, where each group was in the same order and had six subjects. The groups in the same order were referred to as subject groups A to F (Groups A-F). Influences on the answers by the differences among the subject groups are discussed in subsection 4.1.1. The experimental environment was based on the World Robot Competition (WRC), Service Robot Category, which will be held at the World Robot Summit (WRS) in October 2020 [31]. As the details of the layout of the competition field are specified in the WRC Rulebook, we expect that additional experiments and comparative studies can be performed under standard environmental conditions. Figure 7 illustrates the outline of the WRC-compliant field and the execution location of the STs described in subsection 2.3.4. For the experimental conditions, we assumed that the object O that U wanted to be always a pen. In the following, the contents of the experiment are explained using symbols (a) to (g) of Figure 7. Three different pens were placed in P in advance. The subject requested R to carry a pen (a), and R moved to the table P where the pens were placed (b). When R arrived at P (c), there were multiple pens on the table, and U selected one pen. When the object was determined, R grasped the selected pen (d) and moved to U (e, f). Upon arriving at U , the object O was handed over to U (g). In particular, when selecting a pen, dialogue with R or C was inevitably generated, U finally made its own decision, and R moved according to the intention of U . This process is thought to provide a reality of interaction to U .

As described above, we explained the prerequisites that the subject wanted the robot to pick up a pen and asked subjects to complete the task honestly together with the others. Apart from this, the subjects were allowed to interact freely with the robot. Although the basic physical behaviors of the robot did not differ depending on the control mode, the actual three-party interactions differed, as indicated below.

- Experiment of remote control mode (M1)

This condition is PN1 in Table 1. An example of the dialogue is presented in Appendix A.1. U only communicated with C using the chat. In ST1 and ST3, R had to be remotely controlled by C , but in fact, R moved autonomously, while C behaved as though controlling R . In ST2, C interactively displayed the line drawing of the object instruction on U on the User PC.

- Experiment of autonomous control mode (M2)

The condition is PN4 in Table 1. An example of the dialogue is presented in Appendix A.2. U communicated only with R . ST2 was executed as a WOZ test. In particular, C indicated the object with a line drawing on the image and provided operation instructions to R , but these processes were not revealed to U .

- Experiment of autonomous remote control mode (M3)




Figure 7. Experimental environment based on WRC and execution of STs

As indicated in Table 1, two patterns of PN_2 and PN_3 were related to M3, but this time only PN_3 was implemented. An example of the dialogue is presented in Appendix A.3. The task was performed with communication among the three parties U , C , and R . The system adequately satisfied the conditions of M3 without any WOZ tests.

In this experiment, all actions of R were executed within the field of view of U to make it easier to provide the presence of the robot to U and to allow U to feel the impression of the entire robot, including its hardware. However, interaction with C was restricted to the text chat and robot camera images on the User PC. As mentioned previously, the three control modes had different interaction situations, but the actual robot movements were almost the same. If these conditions produced differences in impressions owing to the differences in the control modes, the main factor was not the difference in the impressions of the robot appearance and movement, or visual expressions of the remote operator. It is assumed that this was owing to the difference in the interaction configuration for the physical task execution. We conclude that these settings are important to extract impression differences as appropriately as possible.

3.2 Evaluation Methods

3.2.1 SD Method

Every time one experiment was completed, the subject U was asked to answer the adjective pairs presented in Table 2 using a five-step Likert scale. For the SD method, we referred to the adjective pairs in [32], which proposed adjective pairs for the standard evaluation of service robots. As the first step in the analysis, we evaluated one of the most direct adjective pairs (Q6: ‘Unfriendly–Friendly’) for affinity. We determined whether there was a difference in the population mean in each control mode using the t -test and Holm’s multiple comparison method. If there was no problem with this analysis, factor analysis was performed using the answers to all the questions in Table 2 to gain comprehensive impressions that could not be captured with only one question. When useful factors were extracted, the t -test and Holm’s multiple comparison method were similarly performed to determine the difference between the population means

Table 2. Questions of SD method

No.	Adjective pair		No.	Adjective pair	
1	Unpleasant	Pleasant	13	Irresponsible	Responsible
2	Unkind	Kind	14	Incompetent	Competent
3	Inert	Interactive	15	Foolish	Sensible
4	Moving rigidly	Moving elegantly	16	Fake	Natural
5	Unintelligent	Intelligent	17	Dislike	Like
6	Unfriendly	Friendly	18	Dead	Alive
7	Stagnant	Lively	19	Artificial	Lifelike
8	Unconscious	Conscious	20	Ignorant	Knowledgeable
9	Mechanical	Organic	21	Anxious	Relaxed
10	Apathetic	Responsive	22	Calm	Agitated
11	Awful	Nice	23	Quiescent	Surprised
12	Machinelike	Humanlike			

Table 3. Questions of ranking method

No.	Question
1	In which experiment did you feel affinity for the robot?
2	In which experiment did you feel the intelligence of the robot?
3	In which experiment did you feel a sense of security?
4	In which experiment did you feel friendliness or ease of talking to the remote operator?

of the factor scores among the three control modes. In each analysis, we used the effect size of Cohen's d , which is used extensively in research, and evaluated the results quantitatively. According to Cohen's criteria, $d = 0.8$, $d = 0.5$, and $d = 0.2$ indicate that the effect is large, medium, and small, respectively [33].

3.2.2 Ranking Method

The SD method provided intuitive impressions immediately following the experience of each experiment, while the ranking method provided an impression of looking back on the entire test. Each subject answered the questions in Table 3 after the experiments on the three control modes. In questions 1, 2, and 3, the subjects were requested to answer the ranks from first to third for each control mode. In Q4, the subjects were requested to answer the ranks between the remote control mode and autonomous remote control mode. Q1 concerned the affinity for the robot, which is the central theme of this study. Q2 and Q3 focused on the intellect and sense of security, which are considered as major evaluation factors in addition to the affinity. Q4 was formulated to confirm how the affinity for remote operator C changes depending on the remote control mode (relationship between two parties) or autonomous remote control mode (relationship among three parties). For the analysis of the rank difference owing to the control modes, the Wilcoxon signed-rank test, which is a non-parametric method, and Holm's multiple comparison method were used and for measuring the effect size d , Cliff's d was used [33].

4. Results

4.1 Results of SD Method

4.1.1 Confirmation of Influence of Subject Demographics and Test Order

First, we confirmed the effects of subject demographics on affinity. We divided all the subjects into three classes, namely 18-22 year old males (30 engineering course students), 18-21 year old females (3 engineering course students), and 41-50 year old females (3 university officers). The averages of the questions and answers for each class are presented in Figure 8. Here, the horizontal axis is the question number for each control mode, where Q1 to Q23 are for M1, Q24 to Q46 are for M2, and Q47 to Q69 are for M3. Because the number of data on the latter two classes are limited, they cannot be analyzed statistically. However, it can be observed that the averages tend to be the same, even if the demographics differed. Hence, we used all the data equally to conduct the next step. Accurate statistical analysis of the effects of differences in




Figure 8. Average SD method scores for 3 subject classes




Figure 9. Average SD method scores for subject Groups A–F

subject demographics could be a topic for further study.

As described in Section 3.1, we established six groups of subjects (Groups A–F) with different orders of the control modes. Prior to the analysis, we confirmed the effects of the difference among the groups on the answer. The averages of the questions and answers for each group are presented in Figure 9. It can be observed that all the averages were around the same, even if the subject groups differed.

Furthermore, when one-way analysis of variance was performed for each question, no significant difference ($p < 0.01$) was identified for any question regarding the differences among the population means of the six subjects. According to these results, it was decided to carry out the analysis without considering the influence of the test order. A graph of the average values of the 36 subjects in each control mode (M1 to M3) for each question of the SD method, without considering the test order, is presented in Figure 10, and the values of the mean and standard error (SE) are displayed in Table B1.

4.1.2 Analysis of Single Question

As the first step of the analysis, we analyzed Q6 ('Unfriendly–Friendly'), which was one of the most direct adjective pairs in this study. Figure 11 illustrates the average score (bar graph) and standard error (SE, error bar) of Q6 for each control mode.

Next, Holm's multiple comparison method was performed on the t -test for the difference among the population means in each control mode. As indicated in Table 4, the population means of M2 and M3 were significantly higher than that of M1 ($p < 0.01$). For the effect size of Cohen's d , the difference between M2 and M1 was quite large ($d = 0.829 > 0.8$), and the difference between M3 and M1 was medium to large ($0.5 < d = 0.742 < 0.8$). According to these results, the affinities of M2 and M3 were higher than that of M1, and the difference in the effect sizes indicates that the affinity of M2 was higher than that of M3.




Figure 10. Average values for each question of SD method




Figure 11. Average score and SE of question no. 6

Table 4. Results of multiple comparison method and effect size of question no. 6

Comparison	<i>p</i>	<i>d</i>
M2 $\ddot{\wedge}$ M1	0.003**	0.829
M3 $\ddot{\wedge}$ M1	0.002**	0.742
M2 $\ddot{\wedge}$ M3	0.405	0.170

$\dagger : p < 0.1, * : p < 0.05, ** : p < 0.01$

4.1.3 Factor Analysis

We used the stringing-out method for all the data from the three control modes performed by the 36 subjects. Therefore, the total number of observation data was 108($= 36 \times 3$). The observed variables were the questions of the SD methods (Table 2), and the number of observed variables was 23. We used the Kaiser-Guttman criterion to determine the number of factors. As the eigenvalues of the correlation matrix were 9.07, 1.89, 1.59, 1.35, 0.95, ... in order of magnitude, four factors were determined with eigenvalues of 1.00 or more. Table 5 presents the results of the factor analysis with factor extraction and rotation methods used as maximum likelihood and promax methods, respectively. We used the statistical computing software R version 3.4.4 for the calculations. From the observed variables Table 5, we defined the first factor as vitality, the second as affinity, the third as intellect, and the fourth as inciting. The graph of the averages and SEs of the factor scores are displayed in Figure 12. The statistics are presented in Table 6, and results of the multiple comparison method (*t*-test, Holm's method) and effect sizes (Cohen's *d*) are provided in Table 7. We excluded the factor F4 from the multiple comparison analysis,

Table 5. Factor analysis results
Factor loading matrix

Observed variable (right adjective)	Vitality	F2	F3	F4	h^2
Humanlike	0.87	-0.08	-0.09	0.09	0.62
Lifelike	0.81	-0.12	0.08	0.09	0.62
Organic	0.78	0.03	0.02	0.05	0.66
Conscious	0.67	0.03	0.09	0.16	0.59
Alive	0.54	0.23	0.07	-0.05	0.58
Lively	0.51	0.33	-0.11	-0.10	0.50
Interactive	0.48	0.22	-0.05	-0.09	0.39
Natural	0.47	0.12	0.05	0.05	0.36
Like	-0.01	0.90	-0.09	0.09	0.69
Friendly	0.15	0.65	-0.14	-0.09	0.47
Nice	-0.26	0.64	0.44	0.04	0.66
Pleasant	0.01	0.57	0.02	0.19	0.37
Relaxed	0.08	0.47	-0.07	-0.48	0.50
Kind	0.22	0.42	0.13	-0.01	0.46
Responsive	0.15	0.43	0.24	0.09	0.53
Responsible	0.14	0.32	0.27	-0.10	0.42
Sensible	-0.06	-0.10	0.88	0.05	0.63
Moving elegantly	0.04	-0.08	0.63	-0.12	0.38
Competent	-0.06	0.31	0.54	0.03	0.54
Intelligent	0.40	-0.20	0.56	-0.08	0.53
Knowledgeable	0.07	0.19	0.51	0.02	0.49
Surprised	-0.10	0.43	-0.03	0.73	0.62
Agitated	0.28	-0.11	-0.08	0.67	0.49
Cumulative percentage	0.35	0.66	0.89	1.00	
Factor correlation matrix	F1	F2	F3	F4	
F1	1.00	0.66	0.60	0.00	
F2	0.66	1.00	0.64	-0.07	
F3	0.60	0.64	1.00	0.02	
F4	0.00	-0.07	0.02	1.00	




Figure 12. Average factor score and SE in control modes M1 to M3 and factors F1 to F4

Table 6. Factor score statistics

Factor	M1		M2		M3	
	Mean	SE	Mean	SE	Mean	SE
F1	-0.40	0.17	0.26	0.13	0.14	0.15
F2	-0.41	0.16	0.25	0.13	0.15	0.16
F3	-0.10	0.16	0.14	0.15	-0.04	0.14
F4	-0.00	0.15	0.03	0.15	-0.03	0.13

because the maximum mean difference among the control modes was extremely small at 0.06 (= 0.03 – (-0.03)) in Table 6, and the factor correlation matrix in Table 5 indicates low correlation with the other factors and high independence. The affinity (F2) was significantly higher in M2 and M3 than in M1 ($p < 0.01$). The effect sizes of M2 and M3 from M1 were sufficiently large ($d > 0.8$) and medium to large ($0.5 < d < 0.8$), respectively. According to these results, the affinities of M2 and M3 were improved from M1. Although the effect size of M2 from M3 was slightly positive ($0 < d < 0.2$), it could be concluded that the affinity of M2 was higher than that of M3. A similar tendency was observed for the vitality (F1). For the intellect (F3), the comparison was not statistically significant in any of the multiple comparison methods. However, although the effect sizes exhibited small values, they were in the same order as vitality and affinity.

Table 7. Results of multiple comparison method of factor scores and effect sizes

Comparison	F1 Vitality		F2 Affinity		F3 Intellect	
	<i>p</i>	<i>d</i>	<i>p</i>	<i>d</i>	<i>p</i>	<i>d</i>
M2 $\dot{\iota}$ M1	0.004**	0.773	0.000**	0.840	0.204	0.257
M3 $\dot{\iota}$ M1	0.006**	0.567	0.000**	0.631	1.346	0.060
M2 $\dot{\iota}$ M3	0.425	0.176	0.411	0.128	0.561	0.228

† : $p < 0.1$, * : $p < 0.05$, ** : $p < 0.01$

Table 8. Ranking method statistics in each control mode

Factor	M1		M2		M3	
	Mean	SE	Mean	SE	Mean	SE
Q1 Affinity for <i>R</i>	2.44	0.12	1.47	0.12	2.08	0.11
Q2 Intellect	2.44	0.13	1.53	0.14	2.03	0.09
Q3 Sense of security	1.75	0.13	2.47	0.13	1.83	0.13
Q4 Affinity for <i>C</i>	1.47	0.08	-	-	1.53	0.08




Figure 13. Average order and SE in control modes M1 to M3 and questions Q1 to Q4

Table 9. Results of multiple comparison method for population means of ranking method and effect size

Comparison	Affinity		Intellect		Sense of security	
	<i>p</i>	<i>d</i>	<i>p</i>	<i>d</i>	<i>p</i>	<i>d</i>
M2 $\dot{\iota}$ M1	0.001**	0.611	0.005**	0.500	0.017*	-0.500
M3 $\dot{\iota}$ M1	0.099†	0.278	0.068†	0.389	0.753	0.000
M2 $\dot{\iota}$ M3	0.015*	0.444	0.026*	0.444	0.013*	-0.389

† : $p < 0.1$, * : $p < 0.05$, ** : $p < 0.01$

4.2 Results of ranking method

Figure 13 and Table 8 present the results of the ranking method. The figure and table display the average values of the ranks of the answers of the 36 subjects (first, second, and third), where smaller values indicate more positive answers. The results of the multiple comparison method are presented in Table 9. The *p* values were obtained from Wilcoxon's signed-rank test and modified by Holm's method. The effect size *d* value was calculated using Cliff's *d*. Conversely, a larger *d* indicates a higher rank and smaller rank value. Regarding the average order and effect size, the affinity for *R* (Q1) was positive in the order of M2, M3, and M1, as was the case in the SD method. Regarding the intellect (Q2), the same tendency as the affinity was observed. However, for the sense of security (Q3), the order was reversed, unlike in Q1 and Q2. That is, it was found that M1 and M3 were more secure than M2 from the perspective of the effect size (*d* = -0.500, -0.389). The effect size was extremely small between M1 and M3 (*d* = 0.000), and no significant difference was observed. Regarding the affinity for remote operator *C* (Q4), no significant difference was found from the average ranks of M1 and M3, which had almost the same means at 1.47 and 1.53, respectively, as indicated in Table 8.

5. Discussion

The results in the previous section demonstrate that the affinity of the robot exhibit the order: autonomous control mode, autonomous remote control mode, and remote control mode in both SD and ranking method. The same tendencies of affinity were exhibited in the vitality and intellect when using SD, and ranking method. However, the ranking method indicate that the remote control and autonomous remote control modes had higher sense of security than the autonomous control mode. In the SD method, although there was a direct question about the sense of security (no. 21, 'Anxious–Relaxed'), the means of M2 and M3 were higher than that of M1, which resulted from the factor analysis being incorporated into the affinity (F2). Therefore, the results of the SD method differed from those of the ranking method. Q4 of the ranking method was meant to examine the impression of the remote operator according to the difference between two-party and three-party system. The results demonstrated no significant difference between the two.

According to these results, if we assume that remote functions are still required at present to execute various physical tasks, we can conclude that it is effective to introduce the robot agent explicitly to the user as the autonomous remote control robot, from the perspective of improving the affinity. The dialogue used in this study is a simple command dialogue that is required for physical task instructions, and it is believed that the requested autonomy for the autonomous remote control mode will be achievable at present. Regarding the sense of security, several subjects might have reconsidered the contribution of the operator agent once the experiments were over. Considering that autonomous robot technology remains under development and has not yet been widely used, it is understandable that the subjects desired the sense of security that is constantly observed by humans remotely. There was no significant difference between the impressions of the remote operator in the two control modes in Q4 of the ranking method, but we believe that it is too early to decide that the question has no significance. Although the evaluation of autonomous functions to make the operations easier for remote operators has been researched extensively, the impression of remote operators with different robot configurations has not been substantially evaluated. By analogy with human relationships, it may be more efficient to work while consulting with three people. If the task progresses through the exchange of only two people, apart from the user, the user may experience negative feelings such as alienation. Although it is an ambiguous and complicated problem, the impression of the remote operator is also important for the social implementation of the autonomous remote control robot system, including remote support services. Hence, we consider this as an important future research topic.

6. Conclusions

We conclude that the affinity of autonomous control robots is higher than that of remote control robots, and less than that of autonomous robots, as assumed in Section 1, based on our studies. First, we defined the autonomous remote control robot as a robot performing physical tasks with the robot and operator agents and compared its affinity with those of remote control and autonomous robots. For comparison, we selected an FCT as the most basic task. We defined the task conditions and clarified the scope of this study. The research platform HSR was adopted to conduct the experiments, and the experimental environment was implemented per the WRS 2020 Rulebook, with consideration for future comparisons and additional evaluations. Using the results of the subject experiments, we performed analyses with the SD and ranking method. In each case, higher autonomy resulted in higher affinity. Moreover, similar results were obtained for factors such as vitality and intellect. According to the results, we believe that autonomous remote control robots provide a useful research direction for robots that perform physical tasks in environments where human beings coexist. With such a robot, it is possible to cope with various tasks by remote functions and to improve the autonomous functions sequentially along

with its affinity.

7. Acknowledgment

We would like to thank Dr. Takuto Sakuma and Dr. Luis Contreras-Toledo for their helpful advice in conducting this study.

References

- [1] Jonathan Bohren, Radu Bogdan Rusu, E Gil Jones, Eitan Marder-Eppstein, Caroline Pantofaru, Melonee Wise, Lorenz Mösenlechner, Wim Meeussen, and Stefan Holzer. Towards autonomous robotic butlers: Lessons learned with the pr2. In *2011 IEEE International Conference on Robotics and Automation*, pages 5568–5575. IEEE, 2011.
- [2] Christoph Borst, Thomas Wimbock, Florian Schmidt, Matthias Fuchs, Bernhard Brunner, Franziska Zacharias, Paolo Robuffo Giordano, Rainer Konietzschke, Wolfgang Sepp, Stefan Fuchs, et al. Rollin’justin-mobile platform with variable base. In *2009 IEEE International Conference on Robotics and Automation*, pages 1597–1598. IEEE, 2009.
- [3] Takashi Yamamoto, Koji Terada, Akiyoshi Ochiai, Fuminori Saito, Yoshiaki Asahara, and Kazuto Murase. Development of human support robot as the research platform of a domestic mobile manipulator. *ROBOMECH Journal*, 6(1):4, 2019.
- [4] Yoshiaki Watanabe, Kotaro Nagahama, Kimitoshi Yamazaki, Kei Okada, and Masayuki Inaba. Cooking behavior with handling general cooking tools based on a system integration for a life-sized humanoid robot. *Paladyn, Journal of Behavioral Robotics*, 4(2):63–72, 2013.
- [5] Kensuke Iwata, Tatsuya Aoki, Takato Horii, Tomoaki Nakamura, and Takayuki Nagai. Learning and generation of actions from teleoperation for domestic service robots. In *2018 IEEE/RSJ International Conference on Intelligent Robots and Systems (IROS)*, pages 8184–8191. IEEE, 2018.
- [6] Brian R Duffy. Anthropomorphism and the social robot. *Robotics and autonomous systems*, 42(3-4):177–190, 2003.
- [7] Marcel Heerink, Ben Kröse, Vanessa Evers, and Bob Wielinga. The influence of social presence on acceptance of a companion robot by older people. 2008.
- [8] Ilaria Gaudiello, Elisabetta Zibetti, Sébastien Lefort, Mohamed Chetouani, and Serena Ivaldi. Trust as indicator of robot functional and social acceptance. an experimental study on user conformation to icub answers. *Computers in Human Behavior*, 61:633–655, 2016.
- [9] Tineke Klamer and Somaya Ben Allouch. Acceptance and use of a social robot by elderly users in a domestic environment. In *2010 4th International Conference on Pervasive Computing Technologies for Healthcare*, pages 1–8. IEEE, 2010.
- [10] Kunimatsu Hashimoto, Fuminori Saito, Takashi Yamamoto, and Koichi Ikeda. A field study of the human support robot in the home environment. In *2013 IEEE Workshop on Advanced Robotics and its Social Impacts*, pages 143–150. IEEE, 2013.
- [11] Kotaro Nagahama, Keisuke Takeshita, Hiroaki Yaguchi, Kimitoshi Yamazaki, Takashi Yamamoto, and Masayuki Inaba. A learning method for a daily assistive robot for opening and closing doors based on simple instructions. In *2018 IEEE 14th International Conference on Automation Science and Engineering (CASE)*, pages 599–605. IEEE, 2018.
- [12] Maika Ando, Jotaro Chiba, Shunki Itadera, Jun Nakanishi, Tadayoshi Aoyama, and Yasuhisa Hasegawa. Experimental evaluation of haptic visualization interface for robot teleoperation using onomatopoeia in a haptic recognition task. In *2018 International Symposium on Micro-NanoMechatronics and Human Science (MHS)*, pages 1–4. IEEE, 2018.
- [13] Susumu Tachi, Kazuo Tanie, Kiyoshi Komoriya, and Makoto Kaneko. Tele-existence (i): Design and evaluation of a visual display with sensation of presence. In *Theory and Practice of Robots and Manipulators*, pages 245–254. Springer, 1985.
- [14] Shohei Kato, Shingo Ohshiro, Hidenori Itoh, and Kenji Kimura. Development of a communication robot ifbot. In *IEEE International Conference on Robotics and Automation, 2004. Proceedings. ICRA ’04. 2004*, volume 1, pages 697–702. IEEE, 2004.
- [15] Yosuke Matsusaka, Tsuyoshi Tojo, and Tetsunori Kobayashi. Conversation robot participating

in group conversation. *The IEICE Transactions on Information and Systems (Japanese Edition)*, 84(6):898–908, 2001.

[16] Shinya Fujie, Yoichi Matsuyama, Hikaru Taniyama, and Tetsunori Kobayashi. Conversation robot participating in and promoting human-human communication. *The Transactions of The Institute of Electronics, Information and Communication Engineering (IEICE) A*, 95(1):37–45, 2012.

[17] Takayuki Kanda, Hiroshi Ishiguro, Tetsuo Ono, Michita Imai, and Ryohei Nakatsu. Effects of observation of robot-robot communication on human-robot communication. *The IEICE Transactions on Information and Systems (Japanese Edition)*, 85(7):691–700, 2002.

[18] Takayuki Kanda, Hiroshi Ishiguro, and Toru Ishida. Psychological evaluation on interactions between people and robot. *Journal of the Robotics Society of Japan*, 19(3):362–371, 2001.

[19] Fumitaka Yamaoka, Takayuki Kanda, Hiroshi Ishiguro, and Norihiro Hagita. Interacting with a human or a humanoid robot? *Transactions of Information Processing Society of Japan*, 48(11):3577–3587, 2007.

[20] Kohei Ogawa and Tetsuo Ono. Itaco: Constructing an emotional relationship between human and robot. In *RO-MAN 2008-The 17th IEEE International Symposium on Robot and Human Interactive Communication*, pages 35–40. IEEE, 2008.

[21] Takashi Yamamoto, Yutaro Takagi, Akiyoshi Ochiai, Kunihiro Iwamoto, Yuta Itozawa, Yoshiaki Asahara, Yasukata Yokochi, and Koichi Ikeda. Human support robot as research platform of domestic mobile manipulator. In *Robot World Cup*, pages 457–465. Springer, 2019.

[22] Ron Berenstein, Roy Fox, Stephen McKinley, Stefano Carpin, and Ken Goldberg. Robustly adjusting indoor drip irrigation emitters with the toyota hsr robot. In *2018 IEEE International Conference on Robotics and Automation (ICRA)*, pages 2236–2243. IEEE, 2018.

[23] Jae-Bong Yi and Seung-Joon Yi. Mobile manipulation for the hsr intelligent home service robot. In *2019 16th International Conference on Ubiquitous Robots (UR)*, pages 169–173. IEEE, 2019.

[24] P Peña, M Polceanu, C Lisetti, and U Visser. eeva as a real-time multimodal agent human-robot interface. In *Robot World Cup*, pages 262–274. Springer, 2018.

[25] Ana C Huamán Quispe, Eric Martinson, and Kentaro Oguchi. Learning user preferences for robot-human handovers. In *2017 IEEE/RSJ International Conference on Intelligent Robots and Systems (IROS)*, pages 834–839. IEEE, 2017.

[26] Masatoshi Yamaguchi, Gouki Iwamoto, Yushi Abe, Yuichiro Tanaka, Yutaro Ishida, Hakaru Tamukoh, and Takashi Morie. Live demonstration: A vlsi implementation of time-domain analog weighted-sum calculation model for intelligent processing on robots. In *2019 IEEE International Symposium on Circuits and Systems (ISCAS)*, pages 1–1. IEEE, 2019.

[27] Shunki Itadera, Taisuke Kobayashi, Jun Nakanishi, Tadayoshi Aoyama, and Yasuhisa Hasegawa. Impedance control based assistive mobility aid through online classification of user’s state. In *2019 IEEE/SICE International Symposium on System Integration (SII)*, pages 243–248. IEEE, 2019.

[28] Sunao Hashimoto, Akihiko Ishida, Masahiko Inami, and Takeo Igarashi. Touchme: An augmented reality based remote robot manipulation. In *The 21st International Conference on Artificial Reality and Telexistence, Proceedings of ICAT*, 2011.

[29] Daisuke Sakamoto, Koichiro Honda, Masahiko Inami, and Takeo Igarashi. Sketch and run: a stroke-based interface for home robots. In *Proceedings of the SIGCHI Conference on Human Factors in Computing Systems*, pages 197–200. ACM, 2009.

[30] Laurel D Riek. Wizard of oz studies in hri: a systematic review and new reporting guidelines. *Journal of Human-Robot Interaction*, 1(1):119–136, 2012.

[31] Hiroyuki Okada, Tetsunari Inamura, and Kazuyoshi Wada. What competitions were conducted in the service categories of the world robot summit? *Advanced Robotics*, 33(17):900–910, 2019.

[32] Christoph Bartneck, Dana Kulić, Elizabeth Croft, and Susana Zoghbi. Measurement instruments for the anthropomorphism, animacy, likeability, perceived intelligence, and perceived safety of robots. *International journal of social robotics*, 1(1):71–81, 2009.

[33] Matia Okubo and Kensuke Okada. *Psychological statistics to convey: effect size, confidence interval, and test power*. Keiso Shobo, 2012.

Appendix A. Examples of Dialogue in Three Control Modes

A.1 Example of Dialogue in Remote Control Mode (M1)

C: Hello, *U*.

U: Hello.

C: I am Helper *C*. Nice to meet you. *U*, is there anything you want?

U: I want a pen.

C: All right. Wait a moment please. (*R* moves and arrives at the table.)

C: *U*, which pen do you want?

U: I want the red pen in the front.

C: I understand. (Show the line drawn on the object by *C* on *U*'s PC screen.)

C: I have drawn a red line on the screen. Is this right?

U: Yes. OK.

C: I will take it.

C: *U*, is this OK? (The object in *R*'s hand is displayed on *U*'s PC screen.)

U: OK.

C: Thank you. I will bring it to you. (*R* moves and arrives at *U*.)

C: *U*, here you are. (*U* receives object *O*.)

U: Thank you.

C: You are welcome.

A.2 Example of Dialogue in Autonomous Control Mode (M2)

R: Hello.

U: Hello.

R: Is there anything you want, *U*?

U: *R*, I want a pen.

R: All right. The pen is on the table, so I will move there.

U: OK.

R: Now, I am in front of the table. Which pen do you want?

U: *R*, I want the red pen in the front.

R: All right. I will take it. Wait a moment please.

R: Done. *U*, is this OK? (The object in *R*'s hand is displayed on *U*'s PC screen.)

U: *R*, it is OK.

R: All right. I will bring it to you. (*R* moves and arrives at *U*.)

R: Here you are.

U: *R*, thank you.

R: You are welcome.

A.3 Example of Dialogue in Autonomous Remote Control Mode (M3)

C: Hello.

R: Hello.

U: Hi, everyone.

C: I am Helper *C*. Nice to meet you.

U: Nice to meet you.

C: *U*, is there anything you want?

U: I want a pen.

C: All right. *R*, Do you know where it is?

R: Yes, I know. It is on the table

C: *R*, Would you go to the table?

R: OK, I will go.

R: I am in front of the table. *U*, which pen do you want?

U: *R*, I want the pen on the right.

R: Sorry. I cannot do it. *C*, would you help me?

C: *R*, all right. (Show the line drawn on the object by *C* on *U*'s PC screen.)

C: I have drawn a red line on the screen. *U*, is this right?

U: Yes. OK.

C: All right. I will make *R* take it.

R: Done. *U*, is this OK? (The object in *R*'s hand is displayed on *U*'s PC screen.)

U: *R*, it is OK.

R: All right. I will bring it to you. (*R* moves and arrives at *U*.)

R: *U*, here you are.

U: *R*, *C*, thank you.

C: You are welcome.

R: You are welcome.

Appendix B. Statistics of SD Method

Table B1. Statistics of the SD Method

No.	M1		M2		M3	
	Mean	SE	Mean	SE	Mean	SE
1	3.72	0.11	4.03	0.12	3.86	0.12
2	3.97	0.14	4.42	0.12	3.97	0.17
3	2.89	0.18	3.83	0.13	3.86	0.16
4	3.42	0.14	3.25	0.16	3.56	0.18
5	3.22	0.18	3.72	0.14	3.25	0.14
6	3.17	0.17	3.97	0.15	3.83	0.12
7	2.83	0.16	3.42	0.13	3.47	0.14
8	2.78	0.21	3.31	0.16	3.36	0.18
9	2.56	0.16	3.19	0.16	3.03	0.17
10	3.50	0.18	3.92	0.13	4.08	0.16
11	3.97	0.13	4.22	0.12	4.19	0.13
12	2.31	0.19	2.78	0.17	2.83	0.20
13	3.50	0.17	3.83	0.13	3.61	0.15
14	3.86	0.12	4.11	0.14	3.92	0.14
15	3.83	0.13	3.81	0.12	3.69	0.12
16	3.19	0.15	3.36	0.14	3.36	0.13
17	3.86	0.14	4.31	0.12	4.28	0.13
18	2.97	0.16	3.33	0.12	3.25	0.13
19	2.11	0.17	2.61	0.16	2.42	0.16
20	3.25	0.15	3.56	0.14	3.33	0.14
21	3.72	0.17	4.06	0.16	4.00	0.15
22	2.36	0.15	2.53	0.15	2.31	0.13
23	2.64	0.17	3.03	0.21	3.00	0.20